

A photograph of the IceCube-Gen2 detector in Antarctica at night. The detector consists of several large, cylindrical structures connected by a network of walkways and stairs, all situated on a vast, flat, snow-covered landscape. The sky is a deep, dark blue, filled with numerous stars and the faint, glowing band of the Milky Way galaxy. A vibrant aurora borealis (northern lights) is visible, displaying bright green and blue streaks that dance across the sky, partially obscuring the stars and the Milky Way. The overall scene is a striking combination of natural beauty and human-made scientific infrastructure.

IceCube-Gen2



Notes on construction on ice

The IceCube-Gen2 Collaboration

Albrecht Karle (Univ. Wisconsin-Madison)

IceCube-Gen2

A Vision for the Future of Neutrino Astronomy in Antarctica (arXiv:1412.5106)




Artist's conception
120 strings at 240 m spacing




ICECUBE
GEN2

The next-generation IceCube: from discovery to astronomy

Architecture




- Power and communications architecture: simplified requirements for cable hardware.



ICECUBE
GEN2

IceCube-Gen2 — scope

IceCube and Gen2 on different scales reflecting different energies




ICECUBE
GEN2

Optical sensors

IceCube Upgrade (under construction) primary sensors

IceCube DOM




Diameter 33 cm
10 inch PMT



Directional information
24 x 3 inch PMT
Diameter 36 cm

2 x 8 inch PMT
Smaller diameter 30 cm

Gen2 sensor design studies: MDOM with smaller diameter.



12 x 4 inch PMT
Smaller diameter 30 cm




ICECUBE
GEN2

The Gen2 radio array

200 stations
~500 km²

- A daunting scale!
Impact on Gen2 deployment.
- Highly efficient deployment will be critical.




Heritage:
RICE, ARA, ARIANNA

RNO-G (Greenland) first deployment summer 2020



ICECUBE
GEN2




EHWD-Gen1

Hose reel



Mobile drill/deployment towers

EHWD heating plant: stationary
—> Gen2: mobile



Gen2 hot water drill - changes in requirements

- Mobility: IceCube drill was stationary per season. Gen2 string spacing requires a mobile drill. WDrill will be moved multiple times per season.
- Improved efficiency and lower maintenance technology
- Aim for higher drill speed. (Gen1: 2.1 m/min, Gen2 target close to 3 m/min)



ICECUBE
GEN2

Logistical Support

—> Question 1

1. Logistical Support: IceCube Gen1 had 9.5 million lb of cargo + fuel delivered by plane, more than 300 LC 130 missions. Construction took place simultaneously with South Pole station completion and SPT construction.
2. In recent years logistical support has dropped compared to 10 years ago. This is primarily funding driven. However, funding for logistical support is provided by the project.
3. Strategies for logistical support exist and have been discussed with ASC.
 1. Population of 60 people: —> separate field camp.
 2. Cargo: Traverse is scalable and can take care of fuel (2/3) and possibly cargo but this is not current practice.
4. Successful support will require high level prioritization and strategic planning at NSF's Polar Program.



ICECUBE
GEN2

IceCube, and IceCube-Gen2 - numbers

Item	IceCube actual	IceCube-Gen2 projected
Deep ice strings	86	120
Drill and install seasons at Pole	7 (started 2004)	8 (start 2025)
Sensors/ strings	60	100
Hole depth (m)	2450	2600
Drilled hole diameter (cm)	60	55
Surface detector stations	81	120
Radio stations	none	200
Peak season total population	50	60
Population for radio	0	10
Typical total deployments	90	100
Typical yearly support from contractor (labor hours)	21000	21000
Total cargo delivered including fuel (lbs)	9.5M	9.5M
Fuel only (lbs)	4.1M	4.7M
Drill (lbs)	1.4M	1M
Instrumentation (lbs)	4M	2.75M
Instrumentation, radio (lbs)	0	0.2M
Operating power (kW)	70	150 (including Gen1)
'Dedicated' Herc flights per season	60	≤30 (use of traverse)
Total fuel used (gal)	572k	660k (drilling and camp)
Typical season length	Early November to late January	Early November to early February
Daily data transfer to north via satellite (GB)	105	150 (including Gen1)
Primary method of fuel delivery to Pole	Herc LC-130 aircraft fuel tanker	South Pole Traverse (tractors with sleds)
Population housing method	Station, summer camp	Station, field camp
Field camp	N/A	Housing for up to 60 people
Other large projects during construction	South Pole Station, South Pole Telescope	AIMS, potentially CMB-S4
Work schedule at Pole	3 shifts, 24 hours per day, 6 days per week	3 shifts, 24 hours per day, 6 days per week
Heavy equipment dedicated to project	Loader, skidsteer	Caterpillar Challenger or D8 dozer, 953 loader, skidsteer, transport van



**ICECUBE
GEN2**




IceCube-Gen2 Challenges: Radio array deployment

Drilling 120 holes: IceCube drilling required 7 seasons for 86 strings. Gen2 is planning 8 seasons for 120 strings.

Measures:

1. Drill speed. R&D underway to increase drill speed for Gen2. This can be achieved by increasing water pressure at the drill head from 1000 to ~1500 psi. Note that this will result in fuel savings of order 20 to 30%.
2. Investigate to increase season length by 1 or 2 weeks in February.



ICECUBE
GEN2

IceCube-Gen2 - Challenges: Radio array deployment

Drilling

1. Drilling 600 holes for radio while a challenge, is conceptually straightforward.
2. Scalable solutions exist. ASIG drill is current reference. Requires to people to operate. can be turned on and off.
3. For production, a conceptually similar but more automated design of the British Antarctic Survey is envisioned.

Population: 2 - 3 people/hole/day

*Reminder, why drilling:
the same detector at 100m depth
collects about 3 times more events than
at the surface.*




Deployment


1. Deployment takes most of the labor. about 2/3 of the population will be needed for deployment.
2. Long distances require special safety considerations.
3. Good equipment for transportation: Field shelters, Arctic trucks.



ASIG drill
<https://icedrill.org/equipment/agile-sub-ice-geological-drill.shtml>




Timeline



ICECUBE
GEN2

Gen2 – cables: surface




Field hub:

Deliver optical fiber and power to each string location.
Switch then to in-ice cable

R&D from scintillator array applies directly to Gen2 string architecture.

Considering taking connections and electronics above ground.

The housing approach is still at very early stage.



ICECUBE
GEN2

Surface detector Gen2

- Following the IceTop model, one unit per string.
- Cross calibration
- Cosmic rays at high energies
- Veto x 40

